

## Schedule of Rate

**Name of Work:** Flooring work at Kitchen & store room of Girls Hostel No. 2 NIT Silchar.  
**Completion period:** 30 days.

OR:  
 CR:  
 OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in word	Rate in fig	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	36.00			
2	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25mm thick	Sqm	36.00			

**Total = Rs.**