

OR:  
CR:  
OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in word	Rate in fig	Amount
7	Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 18mm thick.	Sqm	5.00			
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	8.53			
9	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead & refitting the same: Of area 3 sq. metres and below.	Each	2.00			
10	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : (a) For fixed portion - Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15).	Kg	56.00			



OR:  
CR:  
OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in word	Rate in fig	Amount
11	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness	Sqm	14.00			

Total = Rs.



## Schedule of Rate

**Name of Work:** Renovation & minor repairing work at CSE department at NIT Silchar.  
**Location:** Seminar Room, Conference Hall, Store Room & HOD Room  
**Completion period:** 60 days.

OR:  
CR:  
OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in word	Rate in fig	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	228.00			
2	Distempering with 1st quality acrylic washable distemper (ready made) of approved manufacturer and of required shade and colour complete. as per manufacturer's specification. One or more coats on old work	Sqm	228.00			
3	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	98.00			
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. Water thinnable cement primer	Sqm	170.00			
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	37.00			
6	15 mm cement plaster on rough side of single or half brick wall of mix : 1:4 (1 cement: 4 coarse sand)	Sqm	37.00			